

M A R A B U I L D E R S

Er.V.THIRUMARAN., D.C.E.,D.CAD.,
Consulting Civil Engineer
Mobile : 82200 85070

Off:2/188,Chakra nagar,
Thirumohur road,
Y.Othakkadai-625107
Madurai.

Date :

DETAILED & ABSTRACT ESTIMATE

NAME OF WORK

ESTIMATE SHOWING THE PROPOSED CONSTRUCTION OF A RESIDENTIAL BUILDING
IN PLOT No.20, R.SURVEY No.441/3B1 & 441/3B2, AT AVANIAPURAM VILLAGE, MADURAI
SOUTH TALUK, MADURAI CORPORATION, MADURAI DISTRICT.

APPLICANT NAME : Miss.S.LAKSHMI

PROPOSED GROUND FLOOR BUILDUP AREA : 757 Sft

PROPOSED FIRST FLOOR BUILDUP AREA : 757 Sft

Note: 1) Length,Breadth, Depth are mentioned below in terms of Feet and Inches

2)0.13=1.5" ; 0.25 = 3" ; 0.38=4.5" ; 0.50 = 6" ; 0.63=7.5" ; 0.75 = 9";10"=0.85

S.No	Description of work	Nos.	L	B	D	QTY	Rate	Per	Amt
1	Earthwork excavation for the foundation in all soils and sub soils and to full depth as may be directed except hard rock requiring blasting								
	a.Excavation for pillars (Columns)	9	3.50	3.50	6.00	661.50			
		6	4.00	4.00	6.00	576.00			
						1237.50			
					say	1238.00	20	Cft	24760
2	Supplying and filling sand in foundation base	9	3.50	3.50	0.50	55.13			
		6	4.00	4.00	0.50	48.00			
						103.13			
					say	103.00	60	Cft	6180

3	Plain cement concrete with C.C 1:4:8 mix								
	(one part of cement four part of sand and								
	eight part of 40mm broken jelly) for foundatio	9	3.50	3.50	0.75	82.69			
		6	4.00	4.00	0.75	72.00			
						154.69			
					say	155.00	180	Cft	27900
4	R.C.C Column Raft in c.c 1:2:4 (one part of								
	cement two partof sand four 20mm broken								
	jelly) with necessary reinforcement provided	9	3.50	3.50	0.50	55.13			
		6	4.00	4.00	0.50	48.00			
						103.13			
					say	103.00	350	Cft	36050
5	R.C.C Column slope in c.c 1;2:4 (one part of								
	cement two partof sand four 20mm broken								
	jelly) with necessary reinforcement provided	9	3.50	3.50	1.25	137.81			
		6	4.00	4.00	1.25	120.00			
						257.81			
					say	258.00	350	Cft	90300
6	R.C.C Column up to Roof level c.c 1:2:4 mix								
	(one part of cement two part of sand and four								
	part of 20mm broken jelly) with necessary								
	reinforcements provided	9	0.75	0.75	22.50	113.91			
		6	0.75	1.00	22.50	101.25			
						215.16			
					say	215.00	600	Cft	129000
7	Sand filling inside column Trenches	9	3.50	3.50	2.50	275.63			
		6	4.00	4.00	2.50	240.00			
						515.63			
					say	516.00	18	Cft	9288
8	R.C.C Plinth beam in c.c 1:2:4 mix (one								
	part of cement two part of sand and four								
	part of 20mm broken jelly) with necessary								
	reinforcements provided								
	All over the building	1	115.0	0.75	1.50	129.38			
	Cross wall (Vertical wall)	1	15.00	0.75	1.50	16.88			
		1	9.50	0.75	1.50	10.69			
	Cross wall (Horizontal wall)	1	17.50	0.75	1.50	19.69			
		1	8.75	0.75	1.50	9.84			
	<u>Partition wall</u>								
	Cross wall (Horizontal wall)	1	8.75	0.75	1.50	9.84			
		1	4.00	0.75	1.50	4.50			

	Cross wall (Vertical wall)	1	11.00	0.75	1.50	12.38			
						213.19			
					say	213.00	600	Cft	127800
9	Brick work in 9" thick with C.M 1:5 mix (one part of cement and five part of sand) using 1st class chamber burnt bricks for Basement including curing etc								
	All over the building	1	115.0	0.75	3.00	258.75			
	Cross wall (Vertical wall)	1	15.00	0.75	3.00	33.75			
		1	9.50	0.75	3.00	21.38			
	Cross wall (Horizontal wall)	1	17.50	0.75	3.00	39.38			
		1	8.75	0.75	3.00	19.69			
	<u>Partition wall</u>								
	Cross wall (Horizontal wall)	1	8.75	0.75	3.00	19.69			
		1	4.00	0.75	3.00	9.00			
	Cross wall (Vertical wall)	1	11.00	0.75	3.00	24.75			
						426.38			
					say	427.00	220	Cft	93940
10	R.C.C Basement Belt in c.c 1:2:4 mix (one part of cement two part of sand and four part of 20mm broken jelly) with necessary reinforcements provided								
	All over the building	1	115.0	0.75	0.50	43.13			
	Cross wall (Vertical wall)	1	15.00	0.75	0.50	5.63			
		1	9.50	0.75	0.50	3.56			
	Cross wall (Horizontal wall)	1	17.50	0.75	0.50	6.56			
		1	8.75	0.75	0.50	3.28			
	<u>Partition wall</u>								
	Cross wall (Horizontal wall)	1	8.75	0.75	0.50	3.28			
		1	4.00	0.75	0.50	1.50			
	Cross wall (Vertical wall)	1	11.00	0.75	0.50	4.13			
						71.06			
					say	71.00	450	Cft	31950
11	Basement inside plastering in C.M 1:6 mix								
	Living	1	48.00	—	5.00	240.00			
	Kitchen	1	35.00	—	5.00	175.00			
	Bed rm	1	36.50	—	5.00	182.50			
	Bath	1	22.00	—	5.00	110.00			
	Pooja	1	15.00	—	5.00	75.00			
	Bed rm	1	38.50	—	5.00	192.50			
	Toilet	1	25.50	—	5.00	127.50			

	Portico	1	52.00	—	3.00	156.00			
						1258.50			
					say	1259.00	55	Sft	69245
12	Filling basement using earth excauted at site and crusher dust or well sand								
	Living	1	13.00	11.00	5.00	715.00			
	Kitchen	1	8.00	9.50	5.00	380.00			
	Bed rm	1	8.75	9.50	5.00	415.63			
	Bath	1	4.00	7.00	5.00	140.00			
	Pooja	1	4.00	3.50	5.00	70.00			
	Bed rm	1	8.75	10.50	5.00	459.38			
	Toilet	1	8.75	4.00	5.00	175.00			
	Portico	1	10.25	15.75	3.00	484.31			
						2839.31			
					say	2840.00	25	Cft	71000
13	Flooring Plain cement concrete with C.C 1:4:8 mix (one part of cement four part of sand and eight part of 40mm broken jelly) for foundation as per Ceiling Plastering level	1	633	—	0.50	316.50			
					say	317.00	180	Cft	57060
14	Brick work in 9" thick with C.M 1:5 mix (one part of cement and five part of sand) using 1st class chamber burnt bricks for Superstructure including curing etc								
	All over the building	1	115.0	0.75	10.00	862.50			
	Cross wall (Vertical wall)	1	15.00	0.75	10.00	112.50			
		1	9.50	0.75	10.00	71.25			
	Cross wall (Horizontal wall)	1	17.50	0.75	10.00	131.25			
		1	8.75	0.75	10.00	65.63			
	<u>Partition wall</u>								
	Cross wall (Horizontal wall)	1	8.75	0.38	10.00	33.25			
		1	4.00	0.38	10.00	15.20			
	Cross wall (Vertical wall)	1	11.00	0.38	10.00	41.80			
	<u>Deduction</u>								
	Window - W	-1	5.00	0.75	4.50	-16.88			
	Window - W1	-4	4.00	0.75	4.50	-54.00			
	Main door -M.D	-1	3.50	0.75	7.00	-18.38			
	Door - D	-2	3.00	0.75	7.00	-31.50			
	Door - D1	-2	2.50	0.38	7.00	-13.30			
	Ventilator-V	-2	2.50	0.75	2.00	-7.50			
	Open -O1	-1	3.00	0.38	7.00	-7.98			

						1183.85			
					say	1184.00	220	Cft	260480
15	R.C.C Lintel Concrete in c.c 1:2:4 mix (one part of cement two part of sand and four part of 20mm broken jelly) with necessary reinforcements provided								
	All over the building	1	115.0	0.75	0.50	43.13			
	Cross wall (Vertical wall)	1	15.00	0.75	0.50	5.63			
		1	9.50	0.75	0.50	3.56			
	Cross wall (Horizontal wall)	1	17.50	0.75	0.50	6.56			
		1	8.75	0.75	0.50	3.28			
	Partition wall								
	Cross wall (Horizontal wall)	1	8.75	0.38	0.50	1.66			
		1	4.00	0.38	0.50	0.76			
	Cross wall (Vertical wall)	1	11.00	0.38	0.50	2.09			
						66.67			
					say	67.00	450	Cft	30150
16	R.C.C Sunsade & Loft Concrete in c.c 1:2:4 mix (one part of cement two part of sand and four part of 20mm broken jelly) with necessary reinforcements provided, shuttering, barbending complete etc.								
	SUNSHADES	1	6.50	—	1.50	9.75			
		4	5.50	—	1.50	33.00			
	Loft1	2	8.75	—	2.00	35.00			
	Loft2	1	8.00	—	2.00	16.00			
	Loft3	1	9.50	—	2.00	19.00			
						112.75			
					say	113.00	180	Sft	20340
17	R.C.C Roof beam Concrete in c.c 1:2:4 mix (one part of cement two part of sand and four part of 20mm broken jelly) with necessary reinforcements provided								
	All over the building	1	115.0	0.75	1.25	107.81			
	Cross wall (Vertical wall)	1	15.00	0.75	1.25	14.06			
		1	9.50	0.75	1.25	8.91			
	Cross wall (Horizontal wall)	1	17.50	0.75	1.25	16.41			
		1	8.75	0.75	1.25	8.20			
						155.39			
					say	156.00	600	Cft	93600

18	R.C.C Roof slab C.C 1:2:4 mix (one part of cement two part of sand and four part of 20mm broken jelly) with necessary reinforcements provided, shuttering, barbending complete etc.	1	as per	Drawing		757.00			
					say	757.00	320	Sft	242240
19	Ceiling Plastering with C.M 1:3 mix								
	Living	1	13.00	11.00	—	143.00			
	Kitchen	1	8.00	9.50	—	76.00			
	Bed rm	1	8.75	9.50	—	83.13			
	Bath	1	4.00	7.00	—	28.00			
	Pooja	1	4.00	3.50	—	14.00			
	Bed rm	1	8.75	10.50	—	91.88			
	Toilet	1	8.75	4.00	—	35.00			
	Portico	1	10.25	15.75	—	161.44			
						632.44			
					say	633.00	60	Sft	37980
20	Supplying and fixing of doors and windows with Teak & country wood necessary grills and Hardware complete etc.								
	Window - W	1	5.00	—	4.50	22.50			
	Window - W1	4	4.00	—	4.50	72.00			
	Main door -M.D	1	3.50	—	7.00	24.50			
	Door - D	2	3.00	—	7.00	42.00			
	Door - D1	2	2.50	—	7.00	35.00			
	Ventilator-V	2	2.50	—	2.00	10.00			
						206.00			
					say	206.00	550	Sft	113300
21	Inner plastering work in C.M 1:5								
	Living	1	48.00	—	11.00	528.00			
	Kitchen	1	35.00	—	11.00	385.00			
	Bed rm	1	36.50	—	11.00	401.50			
	Bath	1	22.00	—	11.00	242.00			
	Pooja	1	15.00	—	11.00	165.00			
	Bed rm	1	38.50	—	11.00	423.50			
	Toilet	1	25.50	—	11.00	280.50			
	Portico	1	52.00	—	11.00	572.00			
	Deduction								
	Window - W	-1	5.00	—	4.50	-22.50			
	Window - W1	-4	4.00	—	4.50	-72.00			

	Main door -M.D	-1	3.50	—	7.00	-24.50			
	Door - D	-2	3.00	—	7.00	-42.00			
	Door - D1	-2	2.50	—	7.00	-35.00			
	Ventilator-V	-2	2.50	—	2.00	-10.00			
	Open -O1	-1	3.00	—	7.00	-21.00			
						2770.50			
					say	2771.00	60	Sft	166260
22	Outer plastering work in C.M. 1:5 mix								
	All round the building	1	115.0	—	15.50	1782.50			
					say	1783.00	60	Sft	106980
23	Flooring (using Vertified Tiles Flooring)	1	—	—	633	633.00			
	skirting (220.00 Rft)	1				110.00			
						743.00			
					say	743.00	100	Sft	74300
24	Toilet Tiles - Wall tiles	1	22.00	—	7.00	154.00			
		1	25.50	—	7.00	178.50			
	Floor tiles	1	8.75	—	9.50	83.13			
		1	8.75	—	4.00	35.00			
	Kitchen Tiles	1	17.50	—	4.00	70.00			
	Deduction Door	-2	2.50	—	7.00	-35.00			
	Ventilator	-2	2.50	—	2.00	-10.00			
						475.63			
					say	476.00	80	Sft	38080
25	Finishing the elevation with necessary materials and the labours, complete etc					L.S			10000
26	Interior walls colour washing with two coats of distemper over one coat of white cement, one coat of cement Primer and two coats of Acrylic wall putty					L.S			55000
27	Exterior walls colour washing one coat with cement paint over one coat of white cement					L.S			45000
28	Painting wood works and grill with two coats of enamel paints over one coat of primer					L.S			15000
29	Provision for Staircase arrangements					L.S			25000
30	Add 3% for Electric installations								

	contingencies.					L.S			45000
31	Add 3% for sanitary installations, water supply and Drainage works					L.S			45000
32	Unforeseen items					L.S			1817
						TOTAL			2200000
	(RUPEES TWENTY TWO LAKHS ONLY)								


M A R A B U I L D E R S
Er.V.THIRUMARAN,D.C.E.,D.CAD,
Consulting Engineer & Licensed Builder
2/188, Chakra Nagar,
Thirumohur Road, Y.Othakkadai
Madurai-625 107
82200 85070
vthirumaran26@gmail.com

	<u>FIRST FLOOR</u>								
1	R.C.C Column up to Parapet level c.c 1:2:4 mix (one part of cement two part of sand and four part of 20mm broken jelly) with necessary reinforcements provided	9	0.75	0.75	13.50	68.34			
		6	0.75	1.00	13.50	60.75			
						129.09			
					say	29.00	700	Cft	20300
2	Brick work in 9" thick with C.M 1:5 mix (one part of cement and five part of sand) using 1st class chamber burnt bricks for Superstructure including curing etc								
	All over the building	1	115.0	0.75	10.00	862.50			
	Cross wall (Vertical wall)	1	15.00	0.75	10.00	112.50			
		1	9.50	0.75	10.00	71.25			
	Cross wall (Horizontal wall)	1	17.50	0.75	10.00	131.25			
		1	8.75	0.75	10.00	65.63			
	<u>Partition wall</u>								

	Cross wall (Horizontal wall)	1	8.75	0.38	10.00	33.25			
		1	4.00	0.38	10.00	15.20			
	Cross wall (Vertical wall)	1	11.00	0.38	10.00	41.80			
	<u>Deduction</u>								
	Window - W	-1	5.00	0.75	4.50	-16.88			
	Window - W1	-4	4.00	0.75	4.50	-54.00			
	Main door -M.D	-1	3.50	0.75	7.00	-18.38			
	Door - D	-2	3.00	0.75	7.00	-31.50			
	Door - D1	-2	2.50	0.38	7.00	-13.30			
	Ventilator-V	-2	2.50	0.75	2.00	-7.50			
	Open -O1	-1	3.00	0.38	7.00	-7.98			
						1183.85			
					say	1184.00	240	Cft	284160
3	R.C.C Lintel Concrete in c.c 1:2:4 mix (one part of cement two part of sand and four part of 20mm broken jelly) with necessary reinforcements provided								
	All over the building	1	115.0	0.75	0.75	64.69			
	Cross wall (Vertical wall)	1	15.00	0.75	0.75	8.44			
		1	9.50	0.75	0.75	5.34			
	Cross wall (Horizontal wall)	1	17.50	0.75	0.75	9.84			
		1	8.75	0.75	0.75	4.92			
	<u>Partition wall</u>								
	Cross wall (Horizontal wall)	1	8.75	0.38	0.50	1.66			
		1	4.00	0.38	0.50	0.76			
	Cross wall (Vertical wall)	1	11.00	0.38	0.50	2.09			
						97.75			
					say	98.00	600	Cft	58800
4	R.C.C Sunsade & Loft Concrete in c.c 1:2:4 mix (one part of cement two part of sand and four part of 20mm broken jelly) with necessary reinforcements provided, shuttering, barbending complete etc.								
	SUNSHADES	1	6.50	—	1.50	9.75			
		4	5.50	—	1.50	33.00			
	Loft1	2	8.75	—	2.00	35.00			
	Loft2	1	8.00	—	2.00	16.00			
	Loft3	1	9.50	—	2.00	19.00			
	Loft4	1	10.25	—	5.25	53.81			
						166.56			
					say	167.00	245	Sft	40915

5	R.C.C Roof beam Concrete in c.c 1:2:4 mix								
	(one part of cement two part of sand and four								
	part of 20mm broken jelly) with necessary								
	reinforcements provided								
	All over the building	1	115.0	0.75	1.00	86.25			
	Cross wall (Vertical wall)	1	15.00	0.75	1.00	11.25			
		1	9.50	0.75	1.00	7.13			
	Cross wall (Horizontal wall)	1	17.50	0.75	1.00	13.13			
		1	8.75	0.75	1.00	6.56			
						124.31			
					say	124.00	700	Cft	86800
6	R.C.C Roof slab C.C 1:2:4 mix (one part								
	of cement two part of sand and four part								
	of 20mm broken jelly) with necessary								
	reinforcements provided, shuttering,								
	barbending complete etc.	1	as per	Drawing		757.00			
					say	757.00	350	Sft	264950
7	Ceiling Plastering with C.M 1:3 mix								
	Living	1	13.00	11.00	—	143.00			
	Kitchen	1	8.00	9.50	—	76.00			
	Bed rm	1	8.75	9.50	—	83.13			
	Bath	1	4.00	7.00	—	28.00			
	Pooja	1	4.00	3.50	—	14.00			
	Bed rm	1	8.75	10.50	—	91.88			
	Toilet	1	8.75	4.00	—	35.00			
	Balcony	1	7.00	15.75	—	110.25			
						581.25			
					say	582.00	65	Sft	37830
8	Supplying and fixing of doors and windows								
	with Teak & country wood necessary								
	grills and Hardware complete etc.								
	Window - W	1	5.00	—	4.50	22.50			
	Window - W1	4	4.00	—	4.50	72.00			
	Main door -M.D	1	3.50	—	7.00	24.50			
	Door - D	2	3.00	—	7.00	42.00			
	Door - D1	2	2.50	—	7.00	35.00			
	Ventilator-V	2	2.50	—	2.00	10.00			
						206.00			
					say	206.00	700	Sft	144200
9	Inner plastering work in C.M 1:5								
	Living	1	48.00	—	11.00	528.00			

	Kitchen	1	35.00	—	11.00	385.00			
	Bed rm	1	36.50	—	11.00	401.50			
	Bath	1	22.00	—	11.00	242.00			
	Pooja	1	15.00	—	11.00	165.00			
	Bed rm	1	38.50	—	11.00	423.50			
	Toilet	1	25.50	—	11.00	280.50			
	Balcony	1	45.50	—	11.00	500.50			
	Deduction								
	Window - W	-1	5.00	—	4.50	-22.50			
	Window - W1	-4	4.00	—	4.50	-72.00			
	Main door -M.D	-1	3.50	—	7.00	-24.50			
	Door - D	-2	3.00	—	7.00	-42.00			
	Door - D1	-2	2.50	—	7.00	-35.00			
	Ventilator-V	-2	2.50	—	2.00	-10.00			
	Open -O1	-1	3.00	—	7.00	-21.00			
						2699.00			
					say	2699.00	65	Sft	175435
10	Outer plastering work in C.M. 1:5 mix								
	All round the building	1	115.0	—	18.75	2156.25			
					say	2156.00	65	Sft	140140
11	Flooring (using Verified Tiles Flooring)	1	—	—	633	633.00			
	skirting (260.00 Rft)	1				130.00			
						763.00			
					say	763.00	140	Sft	106820
12	Toilet Tiles - Wall tiles	1	22.00	—	7.00	154.00			
		1	25.50	—	7.00	178.50			
	Floor tiles	1	8.75	—	9.50	83.13			
		1	8.75	—	4.00	35.00			
	Kitchen Tiles	1	17.50	—	4.00	70.00			
	Deduction Door	-2	2.50	—	7.00	-35.00			
	Ventilator	-2	2.50	—	2.00	-10.00			
						475.63			
					say	476.00	120	Sft	57120
13	Brick work Parapet wall in 9" thick with								
	C.M 1:5 mix (one part of cement and five								
	part of sand) using 1st class chamber burnt								
	bricks, including curing etc	1	115.0	0.75	3.00	258.75			
					say	259.00	240	Cft	62160
14	Finishing the top of the roof with one								
	course of machine pressed tiles of								
	approved quality laid in c.m. 1:3 mixed								

	with water proofing compound and pointed								
	with the same mortar.	1	as per	Drawing	690.00				
				say	690.00	180	Sft	124200	
15	Finishing the elevation with necessary materials and the labours, complete etc				L.S			20000	
16	Interior walls colour washing with two coats of distemper over one coat of white cement, one coat of cement Primer and two coats of Acrylic wall putty				L.S			60000	
17	Exterior walls colour washing one coat with cement paint over one coat of white cement				L.S			45000	
18	Painting wood works and grill with two coats of enamel paints over one coat of primer				L.S			25000	
19	Provision for Staircase arrangements				L.S			40000	
20	Add 3% for Electric installations contingencies.				L.S			55000	
21	Add 3% for sanitary installations, water supply and Drainage works				L.S			55000	
22	Provision for Over head tank arrangements				L.S			45000	
23	Unforeseen items				L.S			1170	
					TOTAL			1950000	
	(RUPEES NINETEEN LAKHS AND FIFTY THOUSAND ONLY)								


MARA BUILDERS
Er.V.THIRUMARAN,D.C.E.,D.CAD,
Consulting Engineer & Licensed Builder
2/188, Chakra Nagar,
Thirumohur Road, Y.Othakkadai
Madurai-625 107
82200 85070
vthirumaran26@gmail.com

	<u>AMENITIES WORKS</u>								
S.No	Description of work	Nos.	L	B	D	QTY	Rate	Per	Amount
1	Provision for Head Room 9" tk & 8'0"Ht arrangements	1	as per	Drawing		182.00	1200	Sft	218400
2	Provision for Compound wall Brick work 9" tk & 6'0"Ht arrangements		—			100.00	2400	Rft	240000
3	Provision for Compound wall Gate arrangements						L.S		45000
4	Provision for Wooden Closures for all Shelves & Cupboard and Wardrobe works								
	GFloor : Hall Cupboard	1	6.00	—	7.00	42.00			
	Pooja Cupboard	1	3.50	—	7.00	24.50			
	Bed Rm Cupboard	2	8.75	—	3.00	52.50			
		2	4.00	—	7.00	56.00			
	Kitchen Cupboard	1	4.00	—	7.00	28.00			
	FFloor : Hall Cupboard	1	6.00	—	7.00	42.00			
	Pooja Cupboard	1	3.50	—	7.00	24.50			
	Bed Rm Cupboard	2	8.75	—	3.00	52.50			
		2	4.00	—	7.00	56.00			
	Kitchen Cupboard	1	4.00	—	7.00	28.00			
						406.00			
						406.00	600	Sft	243600
5	Providing kitchen top using Jet Block Granite and sink works (20 Rft X 3.00 sft X 1No)					60.00	300	Sft	18000
6	Provision for Septic tank arrangements (6000 Litre Capacity)					6000.00	22	Lit	132000
7	Provision for UG RCC Sump arrangements Size : (5000 Litre Capacity)Approx.. & Laying Tiles					5000.00	24	Lit	120000
8	Provision for Fixtures and Lighting arrangements						L.S		27500
9	Providing Modular kitchen cabinet arrangements						L.S		90000

10	Provision for Borewell with 1.50 H.P								
	Submersible pump arrangements						L.S		80000
11	E.B Permanent III Phase service connection								
	with Distribution board arrangements						L.S		35000
12	Unforeseen items						L.S		500
							Total		1250000
	(RUPEES TWELVE LAKHS AND FIFTY THOUSAND ONLY)								


M A R A B U I L D E R S
Er.V.THIRUMARAN,D.C.E.,D.CAD,
Consulting Engineer & Licensed Builder
2/188, Chakra Nagar,
Thirumohur Road, Y.Othakkadai
Madurai-625 107
82200 85070
vthirumaran26@gmail.com